

路基土石方数量计算表

汕头市龙湖区外砂镇干渠路延伸段（内五线Y662）道路建设工程

桩 号	横 断 面 面 积 (m²)		距离 (m)	挖方分类 及数量 (m³)														填方数量 (m³)			利用方数量及调配 (m³)								借方数量 (m3)及运距 (Km)		弃方数量 (m3)及运距 (Km)		备 注		
				总数量	土						石						本桩利用				填 缺		挖 余		远运利用及纵向调配示意										
	I				II		III		IV		V		VI																						
	挖方	填方			%	数量	%	数量	%	数量	%	数量	%	数量	%	数量	总数量	土	石	土	石	土	石	土	石	土	石								
1	2	3	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33				
K0+000	4.10																																		
K0+020	2.77	0.31	20.00	69			100	69									3	3									3		69						
K0+040	1.58	1.09	20.00	44			100	44									14	14									14		44						
K0+060	0.74	1.72	20.00	23			100	23									28	28									28		23						
K0+080	0.66	1.83	20.00	14			100	14									35	35									35		14						
K0+100	0.50	1.78	20.00	12			100	12									36	36									36		12						
K0+120	0.58	1.70	20.00	11			100	11									35	35									35		11						
K0+140	0.11	2.26	20.00	7			100	7									40	40									40		7						
K0+160		2.42	20.00	1			100	1									47	47									47		1						
K0+180	0.02	2.09	20.00	0			100	0									45	45									45		0						
K0+200	0.59	1.60	20.00	6			100	6									37	37									37		6						
K0+220	0.59	1.67	20.00	12			100	12									33	33									33		12						
K0+240		2.82	20.00	6			100	6									45	45									45		6						
K0+260		2.39	20.00	0			100	0									52	52									52		0						
K0+280		2.33	20.00	0			100	0									47	47									47		0						
K0+300	0.02	3.48	20.00	0			100	0									58	58									58		0						
K0+320	0.11	1.77	20.00	1			100	1									53	53									53		1						
K0+340	0.54	1.41	20.00	7			100	7									32	32									32		7						
K0+360	0.09	1.95	20.00	6			100	6									34	34									34		6						
K0+380	0.18	1.76	20.00	3			100	3									37	37									37		3						
K0+400	0.43	1.77	20.00	6			100	6									35	35									35		6						
K0+420	0.73	1.61	20.00	12			100	12									34	34									34		12						
K0+440	1.24	1.22	20.00	20			100	20									28	28									28		20						
K0+460		2.29	20.00	12			100	12									35	35									35		12						
K0+480	0.07	2.18	20.00	1			100	1									45	45									45		1						
K0+500		2.54	20.00	1			100	1									47	47									47		1						
K0+520		3.28	20.00	0			100	0									58	58									58		0						
小 计				272				272									993	993									993		272						
累 计				272				272									993	993									993		272						

编制：

复核：

审核：

图号：S3-6

路基土石方数量计算表

汕头市龙湖区外砂镇干渠路延伸段（内五线Y662）道路建设工程

桩 号	横 断 面 面 积 (m²)		距离 (m)	挖方分类 及数量 (m³)														填方数量 (m³)			利用方数量及调配 (m³)								借方数量 (m3)及运距 (Km)		弃方数量 (m3)及运距 (Km)		备 注
				总数量	土						石						本桩利用				填 缺		挖 余		远运利用及纵向 调配示意								
					I		II		III		IV		V		VI																		
	挖方	填方			%	数量	%	数量	%	数量	%	数量	%	数量	%	数量	总数量	土	石	土	石	土	石	土		石	土	石					
1	2	3	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33		
K0+520		3.28																															
K0+540		2.90	20.00	0			100	0									62	62									62		0				
K0+560		3.42	20.00	0			100	0									63	63									63		0				
K0+580		3.86	20.00	0			100	0									73	73									73		0				
K0+600		3.16	20.00	0			100	0									70	70									70		0				
K0+620		3.09	20.00	0			100	0									63	63									63		0				
K0+640		2.94	20.00	0			100	0									60	60									60		0				
K0+660		3.36	20.00	0			100	0									63	63									63		0				
K0+680		3.50	20.00	0			100	0									69	69									69		0				
K0+700		2.42	20.00	0			100	0									59	59									59		0				
K0+720	0.04	2.25	20.00	0			100	0									47	47									47		0				
K0+740	0.07	2.00	20.00	1			100	1									42	42									42		1				
K0+760		2.76	20.00	1			100	1									48	48									48		1				
K0+780	0.27	2.61	20.00	3			100	3									54	54									54		3				
K0+800	0.99	1.50	20.00	13			100	13									41	41									41		13				
K0+820	0.10	1.92	20.00	11			100	11									34	34									34		11				
K0+840	0.01	1.94	20.00	1			100	1									39	39									39		1				
K0+860	0.18	1.56	20.00	2			100	2									35	35									35		2				
K0+880		2.05	20.00	2			100	2									36	36									36		2				
K0+900	0.18	1.90	20.00	2			100	2									39	39									39		2				
K0+920	0.01	2.07	20.00	2			100	2									40	40									40		2				
K0+940	0.01	2.49	20.00	0			100	0									46	46									46		0				
K0+960		2.90	20.00	0			100	0									54	54									54		0				
K0+980		2.94	20.00	0			100	0									58	58									58		0				
K1+000		3.26	20.00	0			100	0									62	62									62		0				
K1+020		2.58	20.00	0			100	0									58	58									58		0				
K1+040	0.01	2.24	20.00	0			100	0									48	48									48		0				
小 计				37				37									1362	1362										1362		37			
累 计				309				309									2355	2355										2355		309			

路基土石方数量计算表

汕头市龙湖区外砂镇干渠路延伸段（内五线Y662）道路建设工程

桩 号	横 断 面 面 积 (m²)		距离 (m)	挖 方 分 类 及 数 量 (m³)														填 方 数 量 (m³)			利 用 方 数 量 及 调 配 (m³)								借 方 数 量 (m3)及运距 (Km)		弃 方 数 量 (m3)及运距 (Km)		备 注
				总数量	土						石						本桩利用				填 缺		挖 余		远运利用及纵向调配示意								
	I				II		III		IV		V		VI																				
	挖方	填方			%	数量	%	数量	%	数量	%	数量	%	数量	%	数量	总数量	土	石	土	石	土	石	土		石	土	石					
1	2	3	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33		
K1+040	0.01	2.24																															
K1+060	0.31	1.82	20.00	3			100	3									41	41									41		3				
K1+080	0.01	2.29	20.00	3			100	3									41	41									41		3				
K1+100	0.39	1.40	20.00	4			100	4									37	37									37		4				
K1+120	0.03	2.11	20.00	4			100	4									35	35									35		4				
K1+140		2.01	20.00	0			100	0									41	41									41		0				
K1+160	0.33	1.89	20.00	3			100	3									39	39									39		3				
K1+180		2.84	20.00	3			100	3									47	47									47		3				
K1+200		3.07	20.00	0			100	0									59	59									59		0				
K1+220		3.33	20.00	0			100	0									64	64									64		0				
K1+240	0.85	1.39	20.00	9			100	9									47	47									47		9				
K1+254.348	3.94		14.35	34			100	34									10	10									10		34				
																													</				