

桥梁工程数量表

省道337线潮南路段田心2桥维修工程

第 1 页 共 1 页

项目 材料			单位	桥梁维修										合计	
				立柱	板底	盖梁	桥面铺装	伸缩缝	搭板	挡块修复	护坡修复	围堰	搭设支架		整修施工便道
Q345B钢板条( δ =8mm)			m <sup>2</sup>		56.88										56.88
Q345B钢板条( δ =3mm)			m <sup>2</sup>		0.09										0.09
M12高强螺栓			套		690										690
粘钢板环氧胶			升		170.64										171
C30砼			m <sup>3</sup>						37.5	0.91					38.41
C40砼			m <sup>3</sup>						18.5						18.50
C50砼			m <sup>3</sup>					2.51							2.51
C35小石子混凝土(添外加剂)			m <sup>3</sup>	107.33											107.33
裂缝压注			m		1300		582								1882
环氧砂浆	均厚2. 5cm		m <sup>3</sup>		21.53	6.40									27.93
	均厚1. 0cm		m <sup>3</sup>		7.38										7.38
HPB300钢筋			kg						107	32					139
HRB400钢筋			kg	7132				342	5676	92					13242
植筋	Φ12	深度12cm	kg/根	1430/4480											1430/4480
	Φ12	深度11cm	kg/根					139/144							139/144
	Φ20	深度20cm	kg/根						59/60						59/60
D80毛勒伸缩缝			m					28.9							28.9
拆除、更换止水带			m					56.5							57
油毛毡			m <sup>2</sup>						300						300
C15砼调平层(厚15cm)			m <sup>2</sup>						150						150
凿(清)除 表层砼	均厚2.5cm		m <sup>3</sup>	13.72											14
	均厚2.0cm		m <sup>3</sup>		17.22	5.12									22
	均厚0.5cm		m <sup>3</sup>		3.69										3.7
界面剂			m <sup>2</sup>	549											549
钢筋除锈防锈			m <sup>2</sup>	40	398	80									518
围堰（高2.0m）			m								167				167
搭设支架(宽42m)			m <sup>2</sup>									406			406
爬架(均高7米)			m <sup>2</sup>									7			7
工作平台木板			m <sup>2</sup> /m <sup>3</sup>									483/14.5			483/14.5
防护网			m <sup>2</sup>									406			406
C20混凝土			m <sup>3</sup>								44				44
M7.5浆砌片石			m <sup>3</sup>								63				63
护坡及锥坡填心			m <sup>3</sup>								242				242
拆除混凝土			m <sup>3</sup>								35				35
清基			m <sup>3</sup>	91							90				181
整修便道（宽4.5m）			m										150		150
JN-CF环氧腻子			m <sup>2</sup>	1493	2494	640									4627
FH-T耐候涂料			m <sup>2</sup>	1493	2494	640									4627
临时电力			m											500	500
附注：1. 交通组织设施数量表未计入, 其数量详见S-17。															
2. 临时租用土地3亩, 租期8个月。															

制表:

复核:

审核:

图号: S-3